

Collaborator HyperMAX 6/12

From :
 Business Octane Solutions Pvt Ltd
 JMD Megapolis, 5th Floor
 Sector-48
 Gurgaon 122018
 Ph: 0124-39884088
 Email: Delhisales@businessoctane.com
 5-Sep-2026

Sr. No.	Part Code	Equipment	Unit Selling Price	Qty	Gross Selling Price
Professional Active LED and Touch Display					
1	PAN-125	Panasonic 55" diagonal 4K UHD resolution, 400 nits Professional LCD/LED Display, 24x7 on time with swivel wall mount	86,900	3	2,60,700
2	PAN-127	Panasonic 75" diagonal 4K UHD resolution, Professional interactive LCD/LED Display, 24x7 on time with swivel wall mount	2,25,300	1	2,25,300
3	BO-165	BO 15.6" full HD ultra slim motorized type touch enabled LCD/LED monitor with adjustable angle of view from 90 to 150 degrees along with 1 no. "Show Me" button with orange color illumination and with antiglare screen.	2,35,000	6	14,10,000
Professional Video Codecs					
4	VCO-304	Professional Zoom Room VC System includes four display output codec with HDMI ingestion for presentation sharing with 10.2" Touch screen controller, yearly subscription of Zoom Rooms would be in customer scope.	6,63,000	1	6,63,000
Professional PTZ Camera					
5	BO-166	BO 3 in 1 full 4K PTZ camera with 12X Optical Zoom 70.9 degree FOV with 3 parallel HDMI, USB & LAN video outputs with RS232/TCP-IP ports	1,78,000	4	7,12,000
Professional Integrated Audio Conferencing System					
6	IAS-100EX	AltraCLARITY® AC-1000EX - Integrated Audio Conferencing System Suitable for room size 13 PAX and 17 PAX a). Get highest quality teleconferencing experience which is truly as intimate and natural likely face to face for two large group of people in a video or audio call. b). One no. 360 degree coverage ultra high sensitive conferencing tile microphone array. c). One no. Multi-channel digital signal processor based digital accoustic echo cancellation with 4 mic/line inputs and 2 mic/line outputs, USB input and AEC in all channels. d). USB Connectivity for Teams/Zoom/BYOD video calls. e). One no. 4 channel power amplification with 2 nos FOH & 4 Ceiling speakers for uniform distribution of Audio. f). On-table mute and un-mute button capability. g). Installation, Programming, Testing & Commesionning	15,20,800	1	15,20,800

Sr. No.	Part Code	Equipment	Unit Selling Price	Qty	Gross Selling Price
Professional Control, Switching and Automation System					
7	IAS-102	BO Video & Local Collaborations Enhancer & Simplifier Solution AltraWorkdriverVC™ 1200 including a) Professional 4K UHD resolution Modular chassis based 12x12 HDMI 2.0 with Audio fast & Seamless HDCP compliant matrix switcher for all meeting modes for switching & distributing video and content. b). Whiteboarding & Anotation capability in local as well as in video call on table touch monitors subject to cloud platform supporting the same c) BYOD capability in one cable management system for room camera, displays & audio system for BYOD VC application, also with presentation sharing thorough HDMI capability. d). BO MypcXPLAIN™ capability via inbuilt LED buttons with blue color illumination for fast & seamless presentation show & switch system during Lcoal or Video Meeting. e). Dual Presentations Share & Compare capability to show either same source/laptop on both front displays or two separate sources/images on front displays. f) 10.2" Wi-Fi touch screen with BOSPL SimpliUSE™ GUI for the easy control of various video & Local meeting modes along with detachable wall/table docking station (for wireless touch panel). g) BO remoteless local site whiteboard explanation system - TeleXPLAIN™ for explaining from ordinary cermaic whiteboard during Video and Loca Meeting. h) BO remoteless document show & switch system - PaperXPLAIN™ will be provisioned for sharing documents/objects during Lcoal or Video Meeting. i) One button touch individual participants Zoom in view system "Show Me" for all the participants in video meetings j) Distribution amplifier, USB Hub, USB Switcher, HDMI to USB Convertors, HDMI transmitter and receiver's k) Ethernet type central control processor with more I/o, serial ports. j) Hi-Power relays for rack, lights & power control capability, along with 10A power conditioner with surge protection. l) Four Button meeting mode selector & lighting control system. m) Eight port wired and One access point network capability for controlling and operate to all AV devices. n) Installation, Programming, Testing & Commesionning	25,05,300	1	25,05,300
Professional Cable Management System					
8	BO-172	BO Cable management solution matching with touch content monitors in Silver color with 2 nos 10 Amp Universal power sockets, 2 nos. USB sockets for charging tablets/phones, 6 pass through holes with grommets for routing any kind of AV cables such as HDMI, USB-C, Ethernet etc. along with 3 nos. buttons with blue color illumination.	44,300	3	1,32,900
Professional VC Lighting					
9	BO-161	Telepresence Light Fixture: Providing and fixing of special 2' x 2' VC fixture complete with LED lamps of 4000k. Fixture having special parabolic curved reflector in matt finish to throw indirect light at 45 degree angle so that light fallls on the faces of the participants for bright faces without any glare in video meeting.	35,000	5	1,75,000

Sr. No.	Part Code	Equipment	Unit Selling Price	Qty	Gross Selling Price
Professional Digital Name Tag					
Optional	PAN-132	Panasonic Digital identification systems have transitioned from traditional paper inserts to advanced electronic labels that utilize high-contrast e-paper technology. These smart placards function without internal physical wiring for data, instead relying on wireless frequencies like 2.4 GHz RF or Bluetooth to receive real-time updates from a central server. This wireless architecture allows for sustainable, battery-powered operation that can last for several years, as energy is only consumed during a display change.	41,400	0	-
Professional Display Manager					
10	PVM-110	BOSPL ProVideoMANAGER for 3 nos of 55" Displays Elegant, monolithic structure which is built with modular design with heavy duty square aluminum sections to give high rigidity and is clad with MDF & customer approved PVC Veneer shade from given choices to give one of its kind beautiful free standing structure that houses three displays of 55", multiple cameras, speakers and cables. a)The unique design also allows mounting of the video cameras at perfect height for lowest parallax error to give highest possible eye contact to the far site participants. This also allows you to standardize high quality eye contact across your organization. b)Further it hides all the backs & sides of all displays, cameras, speakers & cables to give an absolute clean front as well as a clean back for high aesthetic appeal. c)This also gives it the capability to be mounted against glass partitions and windows while complimenting aesthetics ,giving you immense flexibility in the conference room design. d)Provision of opening upper & lower flaps ensures easy maintenance.	6,61,000	1	6,61,000
Professional Video Collaboration Table					
11	CLP-238	BOSPL ProCollabSTATION-SCA 6/ SCL 6/ HH 6 a). This Professional Collaboration station in "Semi Circular Arc"/"Semi Circular Local" & "Halfhexa" shape for one side sitting is built with BO proprietary stainless-steel legs which have special capability of holding three HDF tops encased with customer selected PVC veneer, as against normal one top only. This also allows easy reveineering of the top in future. b). Coupled with modesty panels till floor without any visible screws they provide housing for all wires raceways, AV equipments & equipment racks. This eliminates the need for raceways, conduits in the floor and separated rack space for the first time. c). Further the collaboration platform hides all the connecting cables of various equipment embedded on the top such as cable boxes, content monitors, microphones, speaker phones etc. d). It is also provided with telescopic rack for both front & rear rack access both from the front. e). ProCollabStation also has defined & matched space for all equipment's for high aesthetics. Also has marked seating lines. f). ProCollabStation also provides improved view to far site participants. g). Gives your collaboration in a box capability with complete future flexibility as the entire station can be assembled over a weekend, dismantled, packed & moved to another location. h). The tapering design at the end adds a WOW feeling in your conference rooms.	4,65,000	1	4,65,000

Sr. No.	Part Code	Equipment	Unit Selling Price	Qty	Gross Selling Price
12	BO-110	BOSPL ProCollabSTATION for second Row: a). This Professional Collaboration station in semi circular shape is built with extended BO proprietary stainless-steel legs to provide a tiered, clear line of sight over the first row to far-site participants. b). It has full-height modesty panels extending to the floor with zero visible screws, serving as a hidden housing for secondary wire raceways. c). it has self-contained routing connects seamlessly to the front row platform, eliminating the need for core drilling or floor-cut conduits. d). it hides all connecting cables for second-row peripherals, including localized cable boxes, microphones, and content monitors. e). The entire second-row structure can be assembled, dismantled, packed, and relocated over a single weekend.	36,000	12	4,32,000
Professional Cable and Connectors					
13	CAB-101	A set of HDMI, USB, Audio, LAN, Speaker, Control and ethernet cables and connectors		1	4,58,200
Freight, Transit & Site Insurance, Testing & Commissioning Charges					
14	FRE-101	Freight, Transit and Site Insurance		1	2,88,700
15	INS-101	Implementation-Installation, Programming, Testing, Commissioning, Training & as build drawing Charges		1	9,62,200
Total					1,08,72,100

1	Collaborator HyperMAX- CAPEX Price for India (In INR)				₹1,08,72,100
2	Collaborator HyperMAX - CAPEX Price for Outside India (In US Dollar)				\$2,71,803
3	Collaborator HyperMAX- CLASS Service Charges per month for India (In INR)				₹3,77,479
4	Collaborator HyperMAX - CLASS Service Charges per month for outside India (In US Dollar)				\$11,324

Note: GST: Above given price exclusive of GST, GST extra as applicable.

Payment:

a).100% Advance along with commercial clear purchase order.

b). Implementation-Payment against Installation

Delivery: 4-6 weeks from the date of commercial clear P.O.